

PUD DEVELOPMENT PLAN  
**THE HIGHLANDS PHASE 8-REVISED**  
SEPTEMBER 12, 2016

**OWNER/DEVELOPER**

HIGHLAND PROPERTIES COMPANY  
C/O INNOVATIVE MANAGEMENT  
209 GREEN MEADOWS ROAD, SUITE B  
COLUMBIA, MISSOURI 65203

**SITE DATA**

EXISTING ZONING: R-1 PUD  
TRACT SIZE: 5.30 ACRES  
LOCATION: NORTHWEST 1/4 SECTION 2-47-13

WARRANTY DEED RECORDED IN BOOK 254, PAGE 253  
LOTS 827 & 828 THE HIGHLANDS PLAT 8-C, RECORDED IN  
PLAT BOOK 25, PAGE 16

**EXISTING UTILITIES**

SEWER: 6" CITY SEWER MAIN CROSSES EXISTING LOT 828 IN A 30' UTILITY AND DRAINAGE EASEMENT

WATER: 6" MAIN ALONG NORTH SIDE OF STONEHAVEN ROAD AND STUBS ONTO SUBJECT TRACT

GAS: 2" PLASTIC MAIN ALONG SOUTH SIDE OF STONEHAVEN ROAD

ELEC: OVERHEAD ELECTRIC THROUGH THE SUBJECT TRACT TO BE PLACED UNDERGROUND

**GENERAL NOTES**

1. THERE WILL BE A 10' UTILITY EASEMENT ALONG THE STREET FRONTAGE OF ALL LOTS.
2. THERE WILL BE A MINIMUM 16' WIDE EASEMENT DEDICATED FOR ALL SANITARY AND STORM SEWER LINES.
3. ELECTRIC, TELEPHONE, GAS AND WATER LINES WILL BE ADJACENT TO ALL LOTS.
4. THE CUL-DE-SAC WILL HAVE A 47' RADIUS RIGHT-OF-WAY AND 38' RADIUS PAVEMENT.
5. DRIVEWAY ACCESS WILL BE PROHIBITED ALONG OLD PLANK ROAD.
6. A PROPERLY DESIGNED, HARD SURFACED 20' WIDE EMERGENCY ACCESS WAY BETWEEN STONEHAVEN ROAD AND OLD PLANK ROAD IS PROPOSED AS SHOWN WITHIN A 22' WIDE EASEMENT TO BE RECORDED BY SEPARATE DOCUMENT ALONG THE SOUTHERLY SIDE OF LOT 827A. COLLAPSIBLE BOLLARDS WILL BE PLACED AS SHOWN.
7. THE WATER DISTRIBUTION SYSTEM WILL BE DESIGNED BY CITY OF COLUMBIA WATER AND LIGHT ENGINEERING DEPARTMENT.
8. CONTOUR INTERVAL IS TWO (2) FEET.

**PUD NOTES**

1. AREA: 5.30 ACRES
2. MAXIMUM BUILDING HEIGHT:  
PUD: 45 FEET
3. INDIVIDUAL SINGLE FAMILY HOMES. SIZES AND SHAPES WILL VARY.
4. MINIMUM DISTANCE FROM BUILDING TO PERIMETER PROPERTY LINES:  
PUD: 25 FEET FRONT & REAR, 10 FEET ON SIDE YARDS
5. PUD IMPERVIOUS AREA: 1.06 ACRES = 20% (MAXIMUM)  
PUD PERVIOUS AREA: 4.24 ACRES = 80% (MINIMUM)
6. PUD PARKING REQUIRED: 2 PER UNIT x 2 UNITS = 4 SPACES  
PUD PARKING PROVIDED: 4 PER UNIT (2 GARAGE, 2 DRIVEWAY) x 2 UNITS = 8 SPACES (4:1 PER LOT)

**PUD UNIT SUMMARY**

2 SINGLE FAMILY DETACHED UNITS

**PUD DENSITY CALCULATIONS**

GROSS AREA = 5.30 ACRES  
RIGHT-OF-WAY & LOT 527B AREA = 0.35 ACRES  
NET AREA (GROSS MINUS RIGHT-OF-WAY) = 4.95 ACRES

PROPOSED UNITS = 2  
PROPOSED DENSITY = 2 UNITS/4.95 ACRES = 0.40 UNITS/ACRE

**LANDSCAPE NOTES**

EACH LOT SHALL HAVE A MINIMUM OF TWO (2) TREES PLANTED IN THE FRONT YARD.

A MINIMUM OF 60% WILL BE MAINTAINED AS OPEN SPACE SUCH AS NATURAL VEGETATION AND LANDSCAPING.

**CLIMAX FOREST NOTE**

ACCORDING TO THE CITY OF COLUMBIA ARBORIST THE ONLY CLIMAX FOREST IN THE PUD IS LOCATED WITHIN THE REQUIRED STREAM BUFFER, THEREFORE THE ENTIRE CLIMAX FOREST IS PRESERVED.

**DRIVEWAY NOTES**

EACH LOT SHALL HAVE A SINGLE DRIVEWAY OFF STONEHAVEN ROAD THAT IS A MINIMUM TWENTY (20) FEET WIDE.



**SUBDIVISION REGULATION VARIANCES**

1. SECTION 25-47 - TERMINAL STREETS: STONEHAVEN ROAD IS PROPOSED TO BE 2,700'± LONG WITH THE INSTALLATION OF THE CUL-DE-SAC.
2. SECTION 25-48 - SIDEWALKS: THERE ARE NO SIDEWALKS PROPOSED AROUND THE CUL-DE-SAC OR ALONG OLD PLANK ROAD.

BEARINGS ARE REFERENCED TO THE LINES OF THE HIGHLANDS PLAT 8-C, RECORDED IN PLAT BOOK 25, PAGE 16.

**LEGEND**

- B.L. BUILDING SETBACK LINE  
2.0% PROPOSED STREET GRADE  
PROPOSED STORM DRAINAGE STRUCTURE/PIPE  
G PROPOSED GAS MAIN  
W PROPOSED WATER MAIN  
● PROPOSED SANITARY MANHOLE  
• PROPOSED SANITARY CLEAN OUT  
--- G --- EXISTING GAS MAIN  
--- S --- EXISTING SANITARY SEWER  
--- S --- EXISTING SANITARY SEWER  
--- W --- EXISTING WATER MAIN  
--- X --- EXISTING FENCE  
--- OE --- EXISTING OVERHEAD ELECTRIC  
--- P --- EXISTING UTILITY POLE  
--- 640 --- EXISTING CONTOUR  
--- 100 --- APPROXIMATE 100-YEAR FLOOD PLAN  
--- S --- STREAM BUFFER



**TYPICAL LOT LAYOUT**  
(NOT TO SCALE)

APPROVED BY THE COLUMBIA PLANNING AND ZONING COMMISSION THIS \_\_\_\_ DAY OF \_\_\_\_\_, 2016.

RUSTY STROOTMAN, CHAIRPERSON

APPROVED BY THE COLUMBIA CITY COUNCIL THIS \_\_\_\_ DAY OF \_\_\_\_\_, 2016.

BRIAN TREES, MAYOR

SHEELA AMIN, CITY CLERK


**FLOOD PLAN STATEMENT**

THIS TRACT IS NOT LOCATED WITHIN A SPECIAL FLOOD HAZARD AREA (SFHA OR THE 100-YEAR FLOOD PLAN) AS SHOWN BY THE FIRM PANEL NUMBER 29019C02900, DATED MARCH 17, 2011.

**STREAM BUFFER STATEMENT**

THE STREAM BUFFER LIMITS SHOWN ON THIS PLAN ARE INTENDED TO COMPLY WITH THE REQUIREMENTS OF ARTICLE X, CHAPTER 12A OF THE CITY OF COLUMBIA'S CODE OF ORDINANCES. THERE SHALL BE NO CLEARING, GRADING, CONSTRUCTION OR DISTURBANCE OF VEGETATION WITHIN THE BUFFER EXCEPT AS SPECIFICALLY APPROVED BY THE CITY. U.S.G.S. QUADRANGLE MAP "COLUMBIA" WAS USED TO DETERMINE THE TYPE OF STREAM.

**PREPARED BY**



**ALLSTATE CONSULTANTS**

3312 LEMONE INDUSTRIAL BLVD.  
COLUMBIA, MO. 65201  
(573) 875-8799  
allstateconsultants.net

*James R. Jeffries*  
JAMES R. JEFFRIES, PLS. 2900

OCT. 12, 2016  
DATE

