

Facility: Again Street Park

Address: 1200 Again Street

Date of Survey: 04/17/10



1 ACCESS TO THE SITE AND/OR FACILITY

1.1 Exterior Accessible Route (sidewalks, paths, etc.)

- Refer to site plan included with this report: (A) Fill gap between sidewalk and concrete pad for Vita Course Area #17 – 20; see photo 1 next page (C) Replace section of concrete sidewalk that has settled; see photo 2 next page (E) Install 4' wide concrete path from playground sidewalk over to the basketball court – maintain 5% maximum slope as much as is feasible although continuous 5% slope may not be feasible due to existing grades and contours (F) Install a 4' wide concrete path from shelter to horseshoe pit area (G) Install a 4' wide concrete path from sidewalk to one ball field dugout:

Estimated Cost: \$8,246.00



Photo 1



Photo 2

1.2 Parking

- Refer to site plan included with this report: (B) Existing ADA parking space on Again Street needs to be properly striped to delineate a min. 8' wide parking space and min. 8' wide access aisle directly adjacent to the existing curb-cut.
Estimated Cost: \$130.00

1.3 Curb Cuts & Curb Ramps

- Refer to site plan included with this report: (B) Install a truncated dome detectable warning surface that is contrasting with the sidewalk at the existing curb-ramp adjacent to the Again Street ADA parking space.
Estimated Cost: \$1,000.00

1.4 Exterior Ramps

- None exist.

1.5 Exterior Stairs

- None exist.

2 SERVICES

2.1 Building Entrances (exterior doors)

- Not applicable.

2.2 Interior Accessible Route

- Not applicable.

2.3 Interior Ramps

- Not applicable.

2.4 Interior Stairs

- Not applicable.

2.5 Elevators

- Not applicable.

2.6 Platform (wheelchair) Lifts

- None exist.

2.7 Doors (interior, excluding restroom doors addressed in 3.1 and non-public area doors)

- Not applicable.

2.8 Places of Assembly (auditoriums, meeting rooms, gymnasiums, etc.)

- Not applicable.

2.9 Seating and Tables

- Add one accessible picnic table at the shelter. **Estimated Cost: \$850.00**

2.10 Restaurant (including dining areas, snack bars & public use kitchens)

- Not applicable.

2.11 NOT USED

2.12 Business and Mercantile

- No work.

2.13 Dressing and Fitting Rooms

- Not applicable.

2.14 NOT USED

2.15 NOT USED

2.16 Libraries

- Not applicable.

2.17 Storage

- Not applicable.

3 ACCESS TO PUBLIC AMENITIES

3.1 Drinking Fountains

- Refer to site plan included with this report: (D) Replace section of concrete that slopes up to 5% at the drinking fountain so that a level surface (no more than 2% slope in any direction) is available for wheelchair users.

3.2 Restrooms

- None exist.

3.3 Signage

- Not applicable.

3.4 Bathtub & Showers (including locker rooms and dressing rooms)

- Not applicable.

4 BARRIER REMOVAL - OTHER

4.1 Alarms

- Not applicable.

4.2 Public Telephones

- None exist.

4.3 Protruding Objects

- None exist.

4.4 Playgrounds

- Existing playground surface is made up of semi-compacted wood fiber which at the time of the survey was found to be well compacted and appeared to be at least minimally wheelchair accessible. There is a hard surface path from the parking area down to the playground.

4.5 Sinks, Other than Lavatories

- Not applicable.

5 COST ESTIMATE

5.1 Cost Estimate & Notes

- Total facility cost estimate for recommended ADA modifications: **\$10,916.00**

FACILITY SUMMARY		NAME: AGAIN STREET PARK
SECTION HEADING	COST	COMMENTS

1 Access to the Facility

1.1 Exterior Accessible Route	8,246.00	Conc path to basketball, ballfield, horseshoes, repairs
1.2 Parking	130.00	Mark space + access aisle + van access
1.3 Curb Ramps	1,000.00	Replace C-cut @ parking (no detect. warning)
1.4 Exterior Ramps	-	
1.5 Exterior Stairs	-	

2 Services

2.1 Building Entrances	-	
2.2 Interior Accessible Route	-	
2.3 Interior Ramps	-	
2.4 Interior Stairs	-	
2.5 Elevators	-	
2.6 Platform Lifts	-	
2.7 Doors	-	
2.8 Places of Assembly	-	
2.9 Seating and Tables	850.00	Add accessible picnic table @ shelter
2.10 Restaurant	-	
2.11 NOT USED	-	
2.12 Business and Mercantile	-	
2.13 Dressing and Fitting Rooms	-	
2.14 NOT USED	-	
2.15 NOT USED	-	
2.16 Libraries	-	
2.17 Storage	-	

3 Access to Public Amenities

3.1 Drinking Fountains	690.00	Replace conc. pad to be level @ DF
3.2 Toilet Rooms	-	
3.3 Signage	-	
3.4 Bathtubs and Showers	-	

4 Barrier Removal - Other

4.1 Alarms	-	
4.2 Public Telephones	-	
4.3 Protruding Objects	-	
4.4 Work Areas	-	
4.5 Sinks, Other than Lavatories	-	

Total Barrier Removal Cost	10,916.00	
-----------------------------------	------------------	--

Again_Street_Park_School

1200 Again St



- Structure Type**
- Abandoned
 - Administrative
 - Bath House
 - Club House
 - Concession & Restroom & Locker Room (Seasonal Usage)
 - Concession & Restroom (Seasonal Usage)
 - Dug Out
 - Green House
 - Historical
 - Indoor Shelter
 - Maintenance Building
 - Maintenance Shed
 - Pump House
 - Recreation Center
 - Restroom
 - Restroom & Shelter
 - Outdoor Shelter
 - Storage
 - Un_Designated
 - Parks and Recreation Properties



Updated: 8-31-2009 R.JEP: K.VPM/CVGIS-Development/Park_Plans



1 inch = 153.06 feet

This Page Intentionally Left Blank