

Facility: Grindstone Nature Area

Address: 2011 Old Hwy 63 S. Date of Survey: 04/17/10



1 ACCESS TO THE SITE AND/OR FACILITY

1.1 Exterior Accessible Route (sidewalks, paths, etc.)

- Refer to site plan included with this report: (A) Remove ~ 9.5' wide x 50' long section of concrete sidewalk that has slopes and cross-slopes up to 10% and replace with new concrete access walk w/ max. slope of 5% and max. cross-slope of 2% or as close to those maximum slopes as is feasible (B) Patch/grind asphalt to create a smooth transition from parking lot to sidewalk (see photo 1 next page).
Estimated Cost: \$4,384.00



Photo 1

1.2 Parking

- Refer to site plan included with this report: (C) Parking lot has 23 total parking spaces, therefore one ADA parking space is required. Two ADA parking spaces are currently provided, but only one sign is provided. Move the existing ADA parking sign and install on a post at 72" above grade and install a new sign at the other parking space: **Estimated Cost: \$177.00**

1.3 Curb Cuts & Curb Ramps

- None exist.

1.4 Exterior Ramps

- None exist.

1.5 Exterior Stairs

- None exist.

2 SERVICES

2.1 Building Entrances (exterior doors)

- Not applicable.

2.2 Interior Accessible Route

- Not applicable.

2.3 Interior Ramps

- Not applicable.

2.4 Interior Stairs

- Not applicable.

2.5 Elevators

- Not applicable.

2.6 Platform (wheelchair) Lifts

- None exist.

2.7 Doors (interior, excluding restroom doors addressed in 3.1 and non-public area doors)

- Not applicable.

2.8 Places of Assembly (auditoriums, meeting rooms, gymnasiums, etc.)

- Not applicable.

2.9 Seating and Tables

- Add one wheelchair accessible picnic table at the shelter.

Estimated Cost: \$850.00

2.10 Restaurant (including dining areas, snack bars & public use kitchens)

- Not applicable.

2.11 NOT USED

2.12 Business and Mercantile

- Not applicable.

2.13 Dressing and Fitting Rooms

- Not applicable.

2.14 NOT USED

2.15 NOT USED

2.16 Libraries

- Not applicable.

2.17 Storage

- Not applicable.

3 ACCESS TO PUBLIC AMENITIES

3.1 Drinking Fountains

- None exist.

3.2 Restrooms

- Refer to site plan included with this report: (D) Replace non-accessible portable toilet with a wheelchair accessible portable toilet (no cost figured in this estimate) and replace ~ 36 s.f. concrete pad that portable toilet sits on for accessibility (see photo 2 below). **Estimated Cost: \$998.00**



Photo 2

3.3 Signage

- Not applicable.

3.4 Bathtub & Showers (including locker rooms and dressing rooms)

- Not applicable.

4 BARRIER REMOVAL - OTHER

4.1 Alarms

- Not applicable.

4.2 Public Telephones

- None exist.

4.3 Protruding Objects

- None exist.

4.4 Playgrounds

- None exist.

4.5 Sinks, Other than Lavatories

- Not applicable.

5 COST ESTIMATE

5.1 Cost Estimate & Notes

- Total facility cost estimate for recommended ADA modifications: **\$6,409.00**

FACILITY SUMMARY		NAME: GRINDSTONE NATURE AREA
SECTION HEADING	COST	COMMENTS

1 Access to the Facility

- 1.1 Exterior Accessible Route
- 1.2 Parking
- 1.3 Curb Ramps
- 1.4 Exterior Ramps
- 1.5 Exterior Stairs

4,384.00
177.00
-
-
-

Patch asphalt and replace sections of conc path
Raise one sign and add one sign

2 Services

- 2.1 Building Entrances
- 2.2 Interior Accessible Route
- 2.3 Interior Ramps
- 2.4 Interior Stairs
- 2.5 Elevators
- 2.6 Platform Lifts
- 2.7 Doors
- 2.8 Places of Assembly
- 2.9 Seating and Tables
- 2.10 Restaurant
- 2.11 NOT USED
- 2.12 Business and Mercantile
- 2.13 Dressing and Fitting Rooms
- 2.14 NOT USED
- 2.15 NOT USED
- 2.16 Libraries
- 2.17 Storage

-
-
-
-
-
-
-
-
850.00
-
-
-
-
-
-
-
-

Add an access picnic table @ shelter

3 Access to Public Amenities

- 3.1 Drinking Fountains
- 3.2 Toilet Rooms
- 3.3 Signage
- 3.4 Bathtubs and Showers

-
998.00
-
-

Replace conc. pad & provide ADA portable toilet

4 Barrier Removal - Other

- 4.1 Alarms
- 4.2 Public Telephones
- 4.3 Protruding Objects
- 4.4 Work Areas
- 4.5 Sinks, Other than Lavatories

-
-
-
-
-

Total Barrier Removal Cost

6,409.00

--



This Page Intentionally Left Blank