

# Facility: Fairview Park

Address: 1001 Fairview Road Date of Survey: 05/04/10



## 1 ACCESS TO THE SITE AND/OR FACILITY

### 1.1 Exterior Accessible Route (sidewalks, paths, etc.)

- Refer to site plan included with this report: (A) Remove ~ 50 s.f. section of concrete walk that has settled near the intersection of the main sidewalk along Fairview with the sidewalk leading up to the shelter (see photo 1 next page) and replace with new concrete (max. slope of 5% and max. cross-slope of 2%) walk section (B) Remove ~ 100 s.f. section of concrete walk that has settled at the sidewalk leading up to the shelter (see photo 2 next page) and replace with new concrete (max. slope of 5% and max. cross-slope of 2%) walk.

**Estimated Cost: \$2,588.00**



Photo 1



Photo 2

## 1.2 Parking

- No off-street parking is provided at this park site.

## 1.3 Curb Cuts & Curb Ramps

- Refer to site plan included with this report: (C) Install contrasting truncated dome detectable warning surface at walk/drive intersection (see photo 3 below) with Fairview Road.  
**Estimated Cost: \$1,634.00**



Photo 3

## 1.4 Exterior Ramps

- None exist.

## 1.5 Exterior Stairs

- None exist.

## **2 SERVICES**

### **2.1 Building Entrances (exterior doors)**

- Not applicable.

### **2.2 Interior Accessible Route**

- Not applicable.

### **2.3 Interior Ramps**

- Not applicable.

### **2.4 Interior Stairs**

- Not applicable.

### **2.5 Elevators**

- Not applicable.

### **2.6 Platform (wheelchair) Lifts**

- None exist.

### **2.7 Doors (interior, excluding restroom doors addressed in 3.1 and non-public area doors)**

- Not applicable.

### **2.8 Places of Assembly (auditoriums, meeting rooms, gymnasiums, etc.)**

- Not applicable.

### **2.9 Seating and Tables**

- Refer to site plan included with this report: (E) Install a min. 8'x8' concrete pad directly off of the existing sidewalk near the tennis courts for installation of a wheelchair accessible picnic table. Concrete pad to have slopes in any direction not exceeding 2%. **Estimated Cost: \$1,628.00**

### **2.10 Restaurant (including dining areas, snack bars & public use kitchens)**

- Not applicable.

### **2.11 NOT USED**

## 2.12 Business and Mercantile

- Not applicable.

## 2.13 Dressing and Fitting Rooms

- Not applicable.

## 2.14 NOT USED

## 2.15 NOT USED

## 2.16 Libraries

- Not applicable.

## 2.17 Storage

- Not applicable.

# 3 ACCESS TO PUBLIC AMENITIES

## 3.1 Drinking Fountains

- Refer to site plan included with this report: (D) Remove and replace ~ 33 s.f. of settled concrete at the drinking fountain (see photo 4 below) to eliminate change in elevation at the slab; pad should have maximum slope in any direction of 2%.

**Estimated Cost: \$251.00**



Photo 4

### **3.2 Restrooms**

- No work.

### **3.3 Signage**

- No work.

### **3.4 Bathtub & Showers (including locker rooms and dressing rooms)**

- Not applicable.

## **4 BARRIER REMOVAL - OTHER**

### **4.1 Alarms**

- Not applicable.

### **4.2 Public Telephones**

- None exist.

### **4.3 Protruding Objects**

- None exist.

### **4.4 Playgrounds**

- None exist.

### **4.5 Sinks, Other than Lavatories**

- Not applicable.

## **5 COST ESTIMATE**

### **5.1 Cost Estimate & Notes**

- Total facility cost estimate for recommended ADA modifications: **\$6,101.00**

FACILITY SUMMARY		NAME: FAIRVIEW PARK
SECTION HEADING	COST	COMMENTS

**1 Access to the Facility**

1.1 Exterior Accessible Route	2,588.00	Replace sidewalk sections - various
1.2 Parking	-	
1.3 Curb Ramps	1,634.00	Install truncated dome surface @ walk to road
1.4 Exterior Ramps	-	
1.5 Exterior Stairs	-	

**2 Services**

2.1 Building Entrances	-	
2.2 Interior Accessible Route	-	
2.3 Interior Ramps	-	
2.4 Interior Stairs	-	
2.5 Elevators	-	
2.6 Platform Lifts	-	
2.7 Doors	-	
2.8 Places of Assembly	-	
2.9 Seating and Tables	1,628.00	Install conc. pad and access. picnic table
2.10 Restaurant	-	
2.11 NOT USED	-	
2.12 Business and Mercantile	-	
2.13 Dressing and Fitting Rooms	-	
2.14 NOT USED	-	
2.15 NOT USED	-	
2.16 Libraries	-	
2.17 Storage	-	

**3 Access to Public Amenities**

3.1 Drinking Fountains	251.00	Replace conc. pad @ DF
3.2 Toilet Rooms	-	
3.3 Signage	-	
3.4 Bathtubs and Showers	-	

**4 Barrier Removal - Other**

4.1 Alarms	-	
4.2 Public Telephones	-	
4.3 Protruding Objects	-	
4.4 Work Areas	-	
4.5 Sinks, Other than Lavatories	-	

<b>Total Barrier Removal Cost</b>	6,101.00	
-----------------------------------	----------	--

# Fairview\_Park

1001 Fairview Rd.



- Structure Type**
- Abandoned
  - Administrative
  - Bath House
  - Club House
  - Concession & Restroom & Locker Room (Seasonal Usage)
  - Concession & Restroom (Seasonal Usage)
  - Dug Out
  - Green House
  - Historical
  - Indoor Shelter
  - Maintenance Building
  - Maintenance Shed
  - Pump House
  - Recreation Center
  - Restroom
  - Restroom & Shelter
  - Outdoor Shelter
  - Storage
  - Un\_Designated
  - Parks and Recreation Properties



Updated: 8-31-2009 RJEJ K:\P\MC\GIS-Development\Park Plans



1 inch = 165.35 feet

This Page Intentionally Left Blank