

Facility: Fire Station No. 2

Address: 1212 W. Worley Street Date of Survey: 05/14/10



1 ACCESS TO THE SITE AND/OR FACILITY

1.1 Exterior Accessible Route (sidewalks, paths, etc.)

- No work.

1.2 Parking

- Refer to site plan included with this report: (1) Add a van accessible parking space (min. 8' wide parking space with min. 8' wide access aisle) in the existing SE parking area at a location with existing slopes as close to max. 2% as is feasible. New space shall be striped (blue paint) and have an ADA van access parking sign at 72" above grade. **Estimated Cost: \$238.00**

1.3 Curb Cuts & Curb Ramps

- No curb ramps located at the building. Curb ramps located at nearby street intersections have not been evaluated as part of this survey and are being addressed in a separate City sponsored project dealing with Right-of-Way issues.

1.4 Exterior Ramps

- None exist.

1.5 Exterior Stairs

- None exist.

2 SERVICES

2.1 Building Entrances (exterior doors)

- Refer to site plan included with this report: (A) Replace door knob with lever at the NW building entry door. **Estimated Cost: \$305.00**
- Refer to site plan included with this report: (B) Install a door buzzer or intercom at the NW entry door (if door is typically locked) and at the SE apparatus bay door near the new ADA parking space. **Estimated Cost: \$370.00**

2.2 Interior Accessible Route

- No work.

2.3 Interior Ramps

- None exist.

2.4 Interior Stairs

- None exist.

2.5 Elevators

- None exist.

2.6 Platform (wheelchair) Lifts

- None exist.

2.7 Doors (interior, excluding restroom doors addressed in 3.1 and non-public area doors)

- Adjust three door closers in the apparatus bay so that they operate with 5 lbs. force or less. **Estimated Cost: \$60.00**
- Install door hold-open devices on both apparatus bay doors that lead in to the living quarters on both sides of the app bay so that those doors can be held open during tours or other visits from family and or the general public to accommodate access by wheelchair users as there are not level landings at those doors (they have short concrete ramps leading up to the doors) and doors do not have 18" latch side clearance (see photo 1 next page). **Estimated Cost: \$195.00**



Photo 1

2.8 Places of Assembly (auditoriums, meeting rooms, gymnasiums, etc.)

- Not applicable.

2.9 Seating and Tables

- Not applicable.

2.10 Restaurant (includes dining areas, snack bars, vending areas & public use kitchens)

- Not applicable.

2.11 NOT USED

2.12 Business & Mercantile (public & administration areas)

- Not applicable.

2.13 Dressing and Fitting Rooms

- Not applicable.

2.14 NOT USED

2.15 NOT USED

2.16 Libraries

- None exist.

2.17 Storage

- No work.

3 ACCESS TO PUBLIC AMENITIES

3.1 Drinking Fountains

- None exist.

3.2 Restrooms

- There are two restrooms in this building – only one needs to be ADA accessible. The modifications listed here are for the restroom located closest to the app bay (see photo 2 below). Install a braille/tactile ADA restroom sign on the latch side of the door and mounted at 60” above floor to centerline of the sign, relocate the toilet paper dispenser to meet the requirements of ADAAG Fig. 30 (d) and either reconfigure the restroom entry door area or install an automatic door opener with push pad or infra-red controls as the door does not provide the minimum wheelchair maneuvering clearances specified in ADAAG 4.13.6 and Fig. 25.

Estimated Cost: \$5,749.00



Photo 2

3.3 Signage

- Install one directional sign at the new accessible parking area and one at the North main entry area that provides directions to the NW accessible door and/or instructions on using the door buzzer or intercom unit for facility access.

Estimated Cost: \$100.00

3.4 Bathtub & Showers (including locker rooms and dressing rooms)

- No work.

4 BARRIER REMOVAL - OTHER

4.1 Alarms

- None exist.

4.2 Public Telephones

- None exist.

4.3 Protruding Objects

- None exist.

4.4 Work Areas

- No work.

4.5 Sinks, Other than Lavatories

- No work.

5 COST ESTIMATE

5.1 Cost Estimate & Notes

- Total facility cost estimate for recommended ADA modifications: **\$7,017.00**

FACILITY SUMMARY		NAME: FIRE STATION No. 2
SECTION HEADING	COST	COMMENTS

1 Access to the Facility

1.1 Exterior Accessible Route	-	
1.2 Parking	238.00	Add one ADA parking stall
1.3 Curb Ramps	-	
1.4 Exterior Ramps	-	
1.5 Exterior Stairs	-	

2 Services

2.1 Building Entrances	675.00	Install buzzer & lever @ NW bldg. entry
2.2 Interior Accessible Route	-	
2.3 Interior Ramps	-	
2.4 Interior Stairs	-	
2.5 Elevators	-	
2.6 Platform Lifts	-	
2.7 Doors	255.00	Install 2 door hold-open devices & adjust 3 closers
2.8 Places of Assembly	-	
2.9 Seating and Tables	-	
2.10 Restaurant	-	
2.11 NOT USED	-	
2.12 Business and Mercantile	-	
2.13 Dressing and Fitting Rooms	-	
2.14 NOT USED	-	
2.15 NOT USED	-	
2.16 Libraries	-	
2.17 Storage	-	

3 Access to Public Amenities

3.1 Drinking Fountains	-	
3.2 Toilet Rooms	5,749.00	Automate door, add sign & move TPD
3.3 Signage	100.00	Add two directional signs to access. entry
3.4 Bathtubs and Showers	-	

4 Barrier Removal - Other

4.1 Alarms	-	
4.2 Public Telephones	-	
4.3 Protruding Objects	-	
4.4 Work Areas	-	
4.5 Sinks, Other than Lavatories	-	

Total Barrier Removal Cost

7,017.00	
----------	--



This Page Intentionally Left Blank