

Facility: Rock Bridge Park

Address: 201 Miramar Lane Date of Survey: 04/17/10



1 ACCESS TO THE SITE AND/OR FACILITY

1.1 Exterior Accessible Route (sidewalks, paths, etc.)

- Refer to site plan included with this report: (A) Install a new concrete or asphalt access path from new curb-cut at Miramar Lane leading to and connecting the shelter, the two play areas and the basketball court (~ 350 linear feet of 4' wide sidewalk total). Max. slope of access path should be 5% with a max. cross-slope of 2% as much as is feasible. **Estimated Cost: \$10,600.00**

1.2 Parking

- There is no off-street parking at this park site.

1.3 Curb Cuts & Curb Ramps

- Refer to site plan included with this report: (B) Install a contrasting truncated dome curb-cut at Miramar Drive. **Estimated Cost: \$2,500.00**

1.4 Exterior Ramps

- None exist.

1.5 Exterior Stairs

- None exist.

2 SERVICES

2.1 Building Entrances (exterior doors)

- Not applicable.

2.2 Interior Accessible Route

- Not applicable.

2.3 Interior Ramps

- Not applicable.

2.4 Interior Stairs

- Not applicable.

2.5 Elevators

- Not applicable.

2.6 Platform (wheelchair) Lifts

- None exist.

2.7 Doors (interior, excluding restroom doors addressed in 3.1 and non-public area doors)

- Not applicable.

2.8 Places of Assembly (auditoriums, meeting rooms, gymnasiums, etc.)

- Not applicable.

2.9 Seating and Tables

- Add one wheelchair accessible picnic table at the shelter.

Estimated Cost: \$850.00

2.10 Restaurant (including dining areas, snack bars & public use kitchens)

- Not applicable.

2.11 NOT USED

2.12 Business and Mercantile

- Not applicable.

2.13 Dressing and Fitting Rooms

- Not applicable.

2.14 NOT USED

2.15 NOT USED

2.16 Libraries

- Not applicable.

2.17 Storage

- Not applicable.

3 ACCESS TO PUBLIC AMENITIES

3.1 Drinking Fountains

- None exist.

3.2 Restrooms

- None exist.

3.3 Signage

- Not applicable.

3.4 Bathtub & Showers (including locker rooms and dressing rooms)

- Not applicable.

4 BARRIER REMOVAL - OTHER

4.1 Alarms

- Not applicable.

4.2 Public Telephones

- None exist.

4.3 Protruding Objects

- None exist.

4.4 Playgrounds

- Refer to site plan included with this report: (C) Supplement and compact the existing wood fiber surface in the two playground areas (~3,062 s.f. area).
Estimated Cost: \$2,297.00

4.5 Sinks, Other than Lavatories

- Not applicable.

5 COST ESTIMATE

5.1 Cost Estimate & Notes

- Total facility cost estimate for recommended ADA modifications: **\$16,247.00**

FACILITY SUMMARY		NAME: Rock BRIDGE PARK
SECTION HEADING	COST	COMMENTS

1 Access to the Facility

1.1 Exterior Accessible Route	10,600.00	Install conc. path to shelter, playground & bball crt.
1.2 Parking	-	
1.3 Curb Ramps	2,500.00	Add curb-cut @ Miramar St.
1.4 Exterior Ramps	-	
1.5 Exterior Stairs	-	

2 Services

2.1 Building Entrances	-	
2.2 Interior Accessible Route	-	
2.3 Interior Ramps	-	
2.4 Interior Stairs	-	
2.5 Elevators	-	
2.6 Platform Lifts	-	
2.7 Doors	-	
2.8 Places of Assembly	-	
2.9 Seating and Tables	850.00	Add access picnic table @ shelter
2.10 Restaurant	-	
2.11 NOT USED	-	
2.12 Business and Mercantile	-	
2.13 Dressing and Fitting Rooms	-	
2.14 NOT USED	-	
2.15 NOT USED	-	
2.16 Libraries	-	
2.17 Storage	-	

3 Access to Public Amenities

3.1 Drinking Fountains	-	
3.2 Toilet Rooms	-	
3.3 Signage	-	
3.4 Bathtubs and Showers	-	

4 Barrier Removal - Other

4.1 Alarms	-	
4.2 Public Telephones	-	
4.3 Protruding Objects	-	
4.4 Work Areas Playgrounds	2,297.00	Supplement/Compact wood fiber playground surface
4.5 Sinks, Other than Lavatories	-	


Total Barrier Removal Cost

16,247.00	
-----------	--



- Structure Type**
- Abandoned
 - Administrative
 - Bath House
 - Club House
 - Concession & Restroom & Locker Room (Seasonal Usage)
 - Concession & Restroom (Seasonal Usage)
 - Dug Out
 - Green House
 - Historical
 - Indoor Shelter
 - Maintenance Building
 - Maintenance Shed
 - Pump House
 - Recreation Center
 - Restroom
 - Restroom & Shelter
 - Outdoor Shelter
 - Storage
 - Un_Designated
 - Parks and Recreation Properties

09/14/2011 1 inch = 68.34 feet



Page 6 of 6 Feet



NOT TO SCALE

